BRUHAT BANGALORE MAHANAGARA PALIKE

Yelahanka Zone, Electrical Division

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule-B"

Name of Work:-Providing Released Tubular Poles along With Street lights to Gangamma circle Bus-stop to Air Force Gate in ward No11.

Sl No	Qty	Description Of Work	Unit	Approved Rates	
				In figures	In words
1	100	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.3 X 25 + 1 X 25 + 1 X 16 SQ.MM	Per Mtr	177.00	Rupees One Hundred and Seventy Seven Only
2	100	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	Per Mtr	10.30	Rupees Ten and Thirty Paise Only
3	55	Wiring for lighting/power circuit using one of PVC insulated 1100v grade stranded **Aluminium** unsheathed wire single core/multi core cable in open or consealed system of wiring. a)4 sqmm.	Each	7.50	Rupees Seven and Fifty Paise Only
4	2	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps25kA.	Nos	4044.00	Rupees Four Thousand and Forty Four Only
5	6	Supplying and Fixing ..... including all Hardware's etc. complete as per the standard technical specification of BESCOM. RCC Clamp	Each	84.00	Rupees Eighty Four Only
6	6	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.63Amps	Each	234.00	Rupees Two Hundred and Thirty Four Only
7	2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.f)40-63Amps TPN,	Each	1936.00	Rupees One Thousand Nine Hundred and Thirty Six Only
8	54000	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete.16SWG	Sqcm	0.33	Rupees Zero and Thirty Three Paise Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು (ವಿದ್ಯುತ್)
ಬಿ.ಹೆಚ್.ಬಿ.ಪಿ., ಬೆಂಗಳೂರು

9	2	Supply and fixing of 4-pole power contactor with NO/NC contacts on existing wood / panel board using necessary bolts, nuts, washers and wiring etc., complete. d) 100-125 Amps	Each	9915.00	Rupees Nine Thousand Nine Hundred and Fifteen Only
10	6	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and **Copper** conductor single core cable in open or consealed system of wiring.I Group A Materials.g)16 sqmm	Per Mtr	132.00	Rupees One Hundred and Thirty Two Only
11	16000	Supplying and fixing phylum brand hand plastic sheet 3mm thick with necessary niches for fixing switches, regulators etc., and fixing on exisiting wood or metal box using N.F.screws	Sqcm	0.22	Rupees Zero and Twenty Two Paise Only
12	13	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. And M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. a)40X40X6mm	Per Mtr	263.00	Rupees Two Hundred and Sixty Three Only
13	2	Supplying and fixing electro mechanical timer (without contactor) using necessary bolts, nuts and waqshers etc.. Group A, PWD Elec SR 2006-07.	Nos	4200.00	Rupees Four Thousand and Two Hundred Only
15	6	Digging of Pits 1.8 mtr depth for errection of 9 to 10mtr Long Steel/RCC/PSC supports as per approved Drawing.Ordinary Soil	Nos	378.00	Rupees Three Hundred and Seventy Eight Only
16	6	Erection of steel supports 9.0 to 10.00 mtr long suchas 22.68 kg (50 lbs) Rail, 27.22 kg (60 Lbs) Rail IBeam of sizes 200x100mm, 175x90 mm, 125x100mm. Fabricates poles tubular poles in pits of 1.8 mtrDepth, Aligning, Refilling with soil and ramming asapproved drawing	Nos	304.00	Rupees Three Hundred and Four Only
17	6	Pole concreting with CC 1:2:4 (without coping) f) 8mtrs support (400x400x1500mm)	Nos	982.00	Rupees Nine Hundred and Eighty Two Only
18	3	Any Dismantling work 90% of the corresponding erection charges(304x90%=273.6)	Nos	273.60	Rupees Two Hundred and Seventy Three Only
19	2	Transportation using 7.5/10 Tons Lorry Rs. 23 per Kms subjected to a minimum of Rs. 1200/-per day	Days	1200.00	Rupees One Thousand and Two Hundred Only

I am prepared to take up the above work at **0.5%** below (In Words Zero point Five percent below only) the rates quoted in the Schedule 'B'

For VIJAYALAKSHMI ASSOCIATES

Proprietor

CONTRACTOR

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone